BRUHAT BANGALORE MAHANAGARA PALIKE

APPROVED SCHEDULE - B

Name of the Work : Sub estimate for Providing water supply and sanitary for Govt school building at Byatarayanprua in ward no. 07.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Srinivasaiah N.N.	
				In Figures	In Words
1	22.00	Providing and fixing chlorinated poly veny chloride (CPVC) pipes conforming to IS 15778, having thermal stability for **hot and cold water**	M	360.40	Rupees Three Hundred Sixty and
2	22.00	Providing and fixing chlorinated poly veny chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing, this including jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete(internal work exposed on wall), **2532 (32 mmOD) pipe Page No. 105 / Item No. 13.83.4/ PWD SR 2013-14**	M	466.40	Rupees Four Hundred Sixty Six and Forty Paise Only
3	2	KSRB 13-6.2.2: Providing and fixing in position brass stop cock of approved quality **20mm** nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification NO. KBS 13.2.2 / 13.3 **Page No. 97 / Item No. 13.27 / PWD SR 2013-14**	Each	169.60	Rupees One Hundred Sixty Nine and Sixty Paise Only
4	2	KSRB 13-6.1.2: Providing and fixing in position brass bib cock of approved quality **20mm** nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification NO. KBS 13.2.2 / 13.3 **Page No. 96 / Item No. 13.24 / PWD SR 2013-14**	Each	255.46	Rupees Two Hundred Fifty Five and Forty Six Paise Only
5	20.00	KSRB 11-18-1.1: Providing and fixing sand cast iron soil waste and vent pipes 100mm dia with spun yarn soaked in cement slurry and cement mortar 1:2 including cost of materials, labour complete as per specifications. KBS 11.1.10 **Page No. 85 / Item No. 12.47 PWD SR 2013-14**	m	730.34	Rupees Seven Hundred Thirty and Thirty Four Paise Only
6	2	KSRB 11-18-2.1: Providing and fixing sand cast iron soil waste bends 100mm dia with access door, insertion of rubber washers 3mm thick bolts and nut, with spun yarn soaked in cement Slurry and cement mortar 1:2 including cost of materials, labour, testing complete as per specifications. **Page No. 86 / Item No. 12.50 PWD SR 2013-14**	Each	538.48	Rupees Five Hundred Thirty Eight and Forty Eight Paise Only
7	2	KSRB 11-18-19.2: providing and fixing M.S. stays and clamps for sand cast iron pipes of 75mm dia including cost of materials, labour complete as per specifications. **Page No. 91 / Item No. 12.100 PWD SR 2013-14**	No	174.90	Rupees One Hundred Seventy Four and Ninety Paise Only
8	2	Providing and fixing CI Nahani Trap of approved make conforming to ISI specifications and construction of cistern in CC 1:2:4 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). 12.5 cms x 7.5 cms, **Page No. 92 / Item No. 12.113.2 PWD SR 2013-14**	Each	302.10	Rupees Three Hundred Two and Ten Paise Only
9	2	KSRB 12.7.1 : Making connection of drain or sewer line of size 100 to 230mm external dia with existing manhole including breaking into and making good the walls, floors with cement concrete 1:2:4 mix 20mm and downsize granite metal, cement plastered on both sides of mix 1:3 finished with a floating coat of heat cement, and making necessary channels for the drain, including cost of materials, labour charges curing complete as per specifications. **Page No. 75 / Item No. 11.47 PWD SR 2013-14**	nos	1378.00	Rupees One Thousand Three Hundred Seventy Eight Only
10	2	KSRB 13.11.1: Providing and placing on terrace. Polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. **(For 1000 litre capacity)** Specification NO. KBS 13.22 **Page No. 103 / Item No. 13.78 / PWD SR 2013-14**	nos	8831.92	Rupees Eight Thousand Eight Hundred Thirty One and Ninety Two Paise Only
11	6.00	KSRB 12-1.5 : Providing and laying in position to required level or slope 250mm internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints, including cost of materials, labour charges complete as per specifications **Page No. 72 / Item No. 11.5/ PWD SR 2013-14**	m	558.62	Rupees Five Hundred Fifty Eight and Sixty Two Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92